# BRUHAT BANGALORE MAHANAGARA PALIKE, YELAHANKA ZONE

**Executive Engineeer**
**Byatarayanapura Division**
**B.B.M.P., Bangalore - 92**

## DRAFT TENDER SCHEDULE

**Name of work: Construction of RCC Drain and Culverts at Bharathnagra Abubakar Masjid Road in ward no. 06 Byatarayanapura Sub Division**

| Sl. No. | Quantity. | Description | Unit | Rates | |
|---|---|---|---|---|---|
| | | | | In Figures | In Words |
| 1 | 2470.23 | KSRRB 300-1. Earthwork excavation by manual means for roads, drains & similar works in ordinary soil excavated surface levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking of clods complete as per specifications. ~~Item No. 19.1/ PWD SR 2018-19~~ (1) | Cum | 137.80 | Rupees One Hundred Thirty Seven And Paise Eighty Only |
| 2 | 143.55 | KSRRB M2100-10. Providing and laying Plain cement concrete of mix 1:3:6 with OPC @ 220kgs, with crushed 40mm and down size graded granite metal coarse aggregates @0.89cum and fine aggregates @ 0.46cum, in foundation mechanically mixed, placed in foundation and compacted by vibration including curing for 14 days including cost of all materials, labour, HOM curing, form works, scaffolding and centering complete as per specifications. ~~( PWD SR 2018-19 (Page No. 222, Item No.~~ (2) | Cum | 5421.90 | Rupees Five Thousand Four Hundred Twenty One And Paise Ninety Only |
| 3 | 52.80 | Providing and constructing granite / trap / basalt size stone masonry in basement with cement mortar 1:6, edges of stones chistle dressed in courses not less than 15 cms high, bond stones at two m. apart in each course including cost of materials, labour, HOM, scaffolding, curing complete as per specifications. KBS 5.1.13 ~~Page No. 255/ Item No. 34.9/ PWD SR 2018-19~~ (3) | Cum | 5811.98 | Rupees Five Thousand Eight Hundred Eleven And Paise Ninety Eight Only |
| 4 | 2400.00 | KSRB 4-6.4 : Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for vertical surface such as walls at any thickness, including attached pilasters, buttresses, plinth cills and string courses cost of all materials, labour complete as per specifications. Specification No. KBS 4.6.~~(PWD Sr 2018-19 P 16 It 4.31 )~~ (4) | Sqm | 379.48 | Rupees Three Hundred Seventy Nine And Paise Forty Eight Only |
| 5 | 17.55 | KSRB 4-1.7 : : Providing and laying in position plain cement concrete of mix 1:3:6 withOPC cement @ 220kgs, with 20mm and down size graded granite metal coarse aggregates @0.84cum and fine aggregates @0.56cum machine mixed, concrete laid in layers not, exceeding 15cms, thick, well compacted, in foundation and plinth, including cost of all | cum | 5627.54 | Rupees Five Thousand Six Hundred Twenty Seven And Paise Fifty Four Only |
| 6 | 66.00 | KSRB 15.1.3: Providing FLush pointing to coursed stone masonry with cement mortar 1:3, 20 mm deep, after raking joints to depth of 20mm nicely lining, including cost of materials, labour, curing complete as per specifications. ~~Page No. 115/ Item No. 15.1/ PWD SR 2018-19~~ (5) | Sqm | 149.46 | Rupees One Hundred Forty Nine And Paise Forty Six Only |
| 7 | 283.95 | KSRRB M2200-5.9. Providing and laying Design mix M20 with OPC @ 320kgs, with 20mm and down size graded granite metal coarse aggregates @0.69cum and fine aggregates @ 0.46cum, with superplastisiser @3lts confirming to IS9103-1999 Reaffirmed-2008 including cost of materials, labour, HOM | Cum | 5483.38 | Rupees Five Thousand Four Hundred Eighty Three And Paise Thirty Eight Only |

# DRAFT TENDER SCHEDULE

| | | | | | |
|---|---|---|---|---|---|
| | 19.88 | KSRRB M2200-6. Providing T.M.T. steel reinforcement for R.C.C. work including straightening, cutting, bending, hooking, placing in position, lapping and/or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per disign (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM complete as per specification. TMT Bar Fe-500, ~~Page No. 229/ Item No. 28.8.2, PWD SR 2018-19~~ (6) | Tonne | 72326.98 | Rupees Seventy Two Thousand Three Hundred Twenty Six And Paise Ninety Eight Only |
| 9 | 82.50 | **Providing and fixing RCC precast cover slab of 250mm thick** made out of CC 1:2:4 and jelly 20mm and down size with steel reinforcement, including form work, lift charges, curing and concrete finished surfaces on both sides etc, complete and as per drawing and the directions of Engineer in-charge. ~~(Data Rate)~~ (7) | Sqm | 5418.00 | Rupees Five Thousand Four Hundred Eighteen Only |
| 10 | 813.60 | **Providing and fixing RCC precast cover slab of 100mm thick** for drain in cement concrete 1:1.5:3 using graded granite jelly 20mm and down size with steel reinforcement, including form work, lift charges, curing and concrete finished surfaces on both sides etc, complete and as per drawing and the directions of Engineer in-charge. ~~(Data Rate)~~ | sqm | 2337.00 | Rupees Two Thousand Three Hundred Thirty Seven Only |
| 11 | 2470.23 | KSRRB M100-2. Loading and Unloading of stone boulders by manual means complete as per specification MORTH-100/chapter-1 ~~Page No. 136/ Item No. 17.1/ PWD SR 2018-19~~ (8) | Cum | 71.02 | Rupees Seventy One And Paise Two Only |

**Executive Engineer**
**Byatarayanapura Division**
**BBMP, Bangalore - 92**

**Note:**

1 Item for which no rate of price has been entered in will not be paid for by the Employer when executed and shall be deemed covered by the other rates and prices in the bill of quantities (refer: ITB Clause 7.2 and CC Clause 33.2)
2 Unit rates and prices shall be quoted by the tender in indian rupees.
3 Where there is a discrepancy between the rate in figures and words the rates in words will govern (ITB Clause 19.1(a)
4 Where there is a discrepancy between the rate and the line item total resulting from multyplying the unit rate by quantity the unit rate quoted shall govern (ITBClause 19.1(b)

ಅಂಕಿಕೆ ( ) ರಲ್ಲಿ ವಿವರಿಸಿರುವಂತೆ ಅಂಶಗಳ ಬಗ್ಗೆ
ಕಾರ್ಯಪಾಲಕ ಅಭಿಯಂತರರು( ) ರವರು
ವೃಥೀಕರಿಸಿಕೊಳ್ಳುವ ಹಾಗೆ ಒಳಪಡಿಸಿ ದಿ.ಟಿ.ಎಸ್
ಅಂಗೀಕರಿಸಿದೆ.
ಕರಾರು ಪತ್ರದ ಶೆಡ್ಯೂಲ್‌ನ ವಿವರಣೆಯಂತೆ
ವಿಷ್ಣುವರ್ಧನ ಅಯ್ಯಂಗಾರ್ ಬಿಲ್ಡರ್ಸ್
ವಿಶ್ವಾಸಿಗಳ ಒಟ್ಟು ಸಂಖ್ಯೆ : 08
ರದ್ದುಪಡಿಸುವ ಒಟ್ಟು ಪಟುಂಗಳ ಸಂಖ್ಯೆ :
2/6/2020